

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-171-20988-00-00  
Spot: SESWNESE Sec/Twnshp/Rge: 23-16S-33W  
1429 feet from S Section Line, 775 feet from E Section Line  
Lease Name: GRIFFITH Well #: 2-23  
County: SCOTT Total Vertical Depth: 4810 feet

Operator License No.: 9855  
Op Name: GRAND MESA OPERATING COMPANY  
Address: 1700 N WATERFRONT PKWY BLDG 600  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4150		WITH 2 SX CMT
PROD	5.5	4812	0	WITH 225 SX CMT
SURF	8.625	221		WITH 170 SX CMT

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/24/2014 9:00 AM  
Plug Co. License No.: 32810 Plug Co. Name: PROFESSIONAL PULLING SERVICES LLC  
Proposal Rcvd. from: JOHN JOHNSON Company: GRAND MESA Phone: (620) 617-3357

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 02/25/2014 10:30 AM KCC Agent: KEN JEHLIK

**Actual Plugging Report:**

2/24/14: CIBP @ 4150' WITH 2 SX CMT. PERFORATE @ 2340'. SPOT 50 SX CMT WITH 50# HULLS IN THE LAST 25 SX CMT. (25 SX CMT OUTSIDE THE CASING). PRESSURE TO 1400#. SPLIT COLLAR SHOT @ 1430'. COULD NOT PULL 5 1/2" AT 120000#. PUMP 50 SX PLUG THROUGH SPLIT COLLAR. SPLIT COLLAR @ 1050'. COULD NOT PULL 5 1/2" AT 120000#. PUMP INTO SPLIT COLLAR AT 2 1/2 BPM AT 600#. SDFN. 2/25/14: INJECTION RATE DOWN 5 1/2' CASING THROUGH SPLIT COLLAR AT 1050'. 3 BPM @ 600#. PUMP 150 SX CMT WITH 100# HULLS AFTER THE FIRST 50 SX CMT. DISPLACE 50 SX CMT OUT THE SPLIT COLLAR & LEAVE THE 5 1/2" CASING FULL OF CMT. SHUT IN AT 500#. PUMP 150 SX CMT DOWN THE 5 1/2" X 8 5/8" ANNULUS @ 300#. SHUT IN AT 250#.

**Perfs:**

Top	Bot	Thru	Comments
4207	4210		

**KCC WICHITA**  
**MAR 04 2014**  
**RECEIVED**

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: CSG

District: 01

RECEIVED  
MAR - 3 2014  
KCC DODGE CITY

Signed Ken Jehlik  
3/05/14 (TECHNICIAN)