

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-151-22430-00-00
Spot: NWNWSE Sec/Twnshp/Rge: 26-29S-15W
2310 feet from S Section Line, 2310 feet from E Section Line
Lease Name: EADS B Well #: 1
County: PRATT Total Vertical Depth: 4803 feet

Operator License No.: 31980
Op Name: LOTUS OPERATING COMPANY, L.L.C.
Address: 100 S MAIN, STE 420
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	987		WITH 460 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 02/06/2014 6:00 PM
Plug Co. License No.: 5929 Plug Co. Name: DUKE DRILLING CO., INC.
Proposal Rcvd. from: GALEN ROACH Company: DUKE DRILLING CO., INC. Phone: (316) 267-1331

Proposed Plugging Method: 1ST PLUG AT 4801' WITH 50 SX CMT. 2ND PLUG AT 1020' WITH 50 SX CMT. 3RD PLUG AT 270' WITH 40 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: NONE
Date/Time Plugging Completed: 02/06/2014 8:00 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

Perfs:

RAN 1" TO 100' DOWN 8 5/8" & 13 3/8" CIRCULATED TO SURFACE WITH 350 SX CMT. 8 5/8" BASKET @ 250'. 1ST PLUG AT 4801' WITH 50 SX CMT. 2ND PLUG AT 1020' WITH 50 SX CMT. 3RD PLUG AT 270' WITH 40 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: DP

District: 01

Signed Eric Maclaren
3/07/14 (TECHNICIAN)

RECEIVED
FEB 11 2014
KCC DODGE CITY

KCC WICHITA

Form CP-2/3

FEB 18 2014

RECEIVED

Handwritten initials