

3-29

198

T-33
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 119-20,301-00

CSW S 400, SEC. 22, T 33 S, R 29 W/E

1320' feet from S section line

3960' feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 04824

Lease Name Bender Well # 1-22

Operator: MESR Operating LTD Ptnr
Name &
Address P.O. Box 2009

County Meade 199.81

Well Total Depth 6148 feet

Amarillo, Tx. 79189

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 7/8 feet 1489

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ O&A _____

Other well as hereinafter indicated _____

Plugging Contractor SARGENTS CASING PULLING License Number 6547

Address 620 S LINCOLN, LIBERAL KANSAS 67901

Company to plug at: Hour: 9:30 AM Day: 28 Month: 3 Year: 19 90

Plugging proposal received from _____

(company name) _____ (phone) _____

were: 5 1/2 AT 6148, PBTDT AT 6109, Parts AT 5742-5758, 5817-5870, 6066-6092
2nd set Part 3096-3104. ① CIBP AT 5720 with 2sv cement on top ② Load hole
with mud CIBP AT 3075 with 2sv cement on top, Shoot pipe face point,
Load hole with mud, ③ Pump 50sv AT 1540' ④ pump 30sv AT 650'
⑤ Pump 10sv AT 40ft-0 Cut off 8 7/8 AT 3' below GL weld cap on

Plugging Proposal Received by _____

(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 4:00 PM Day: 29 Month: 3 Year: 19 90

ACTUAL PLUGGING REPORT ① plug Load hole with mud set CIBP AT 5720

dump 2sv on top with briler, 2nd plug set CIBP AT 3075, dump 2sv

cement on top with briler, ③ Shoot pipe AT 2206, Pump 50sv

AT 1540'-1390', ④ plug Pump 30sv AT 650'-490', ⑤ plug Pump

10sv AT 40ft-0. Cut off 8 7/8 AT 3' below GL weld cap on

Heavy mud between all plugs

Remarks: Used common cement (Portland 42) Recovered 2206' of 5 3/8 casing

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 4-6-90

Signed Glen R. Barber
(TECHNICIAN)

INV. NO. 27796