

State of Kansas



15-007-30259-0000

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JOHN C. WOELK Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JAN 10 1966
1-10-66
CONSERVATION DIVISION
Wichita

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. H. L. Caldwell of K W B Oil Property Mang. has this date requested permission to plug the following described well:

Mr. Caldwell guarantees payment of the plugging fee.

Operator's full Name: K W B Oil Property Management, Inc.

Complete Address: 913 Kennedy Bldg., Tulsa, Oklahoma

Lease Name: Cook-McCullough Well No. # 1

Location: SW NW Sec. 9 Twp. 34 Rge. 12 (E)(W) W

County Barber Total Depth 4752' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Caldwell was instructed to plug the well as follows:

429' of 8 5/8" surface pipe, cement circulated with 250 sacks.
Fill hole with drilling mud to 280', 1st cementing plug, bridge
with hulls, and cement with 25 sacks. Fill hole with drilling mud
to 40', 2nd cementing plug, bridge with hulls, and cement with 10
sacks to base of cellar. Bridge rat and mouse holes and cement with
4 sacks.

Very truly yours,

Archie Elving
Conservation Division Agent