

State of Kansas



WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

SEP 19 1967

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

CONSERVATION DIVISION  
Wichita, Kansas

Intent to Drill,  
filed September 27, 1967.

Dear Sir:

Mr. Charles Craig of Cities Service Oil Co. has this  
date requested permission to plug the following described well:

Mr. Craig guarantees payment of the plugging fee.

Operator's full Name: Cities Service Oil Company

Complete Address: P. O. Box, 308, Great Bend, Kansas 67530

Lease Name: Neilson "A" Well No. # 1

Location: C NE SW Sec. 18 Twp. 31 Rge. 17 (E) (W) W

County Comanche Total Depth 5465' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Craig was instructed to plug the well as follows:

510' of 8 5/8" surface pipe, cement circulated with 275 sacks. Fill  
hole with drilling mud to 400', 1st cementing plug, bridge with 1/2 sack  
of hulls, and cement with 25 sacks. Fill hole with drilling mud to 40',  
2nd cementing plug, bridge with 1/2 sack of hulls, and cement with 10  
sacks to base of cellar. Bridge and cement rat & mouse holes with 4 sack

Very truly yours,

Archie Elving  
Conservation Division Agent