

CP2

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
OCT 20 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Hanna of Anadarko Prod. Co. has this

date requested permission to plug the following described well:

Mr. Hanna guarantees payment of the plugging fee.

Operator's full Name: Anadarko Production Co.

Complete Address: Box 351 Liberal, Ks

Lease Name: Uhl B Well No. 1

Location: 1980' FEL & 660' FNL ^{C NW NE} Sec. 19 ²⁹ Twp. 31s Rge. 17 (E)(W) W

County: Comanche Total Depth 5121 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Hanna was instructed to plug the well as follows:

410 ft of 8 5/8 surface pipe cemented with 320 sacks. Fill
hole to 650 ft. Pump 40 sacks cement. Fill hole to 350 ft.

Pump 40 sacks cement. Mud to 40 ft. plug. 1/2 sack hulls.

15 sacks cement to surface. 5 sacks cement in rat hole.

Halliburton Cementing Co. Great Bend, Ks

Very truly yours,

[Signature]
Conservation Division Agent