

*Y* KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 5 1966  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Petroleum, Inc.

Complete Address: 300 West Douglas, Wichita, Kansas

Lease Name Trummel "B" Well No. # 1

Location Approx. C NE Sec. 12 Twp. 31 Rge. 17 (E) (W) W

County Comanche Total Depth 5009'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Garvey Drilling Company

Address: R. R. # 2, Great Bend, Kansas License No.

Operation Completed: Hour 1:30AM Day 1st Month Dec. Year 1966

The Above well was plugged as follows:

530' of 8 5/8" surface pipe, Cement circulated with 350 sacks. Hole  
was filled with drilling mud to 500', 1st cementing plug, bridged with  
2 sacks of cement and 1/2 sack of hulls on fluid at 500', and cemented  
with 23 sacks. Hole was filled with drilling mud to 40', 2nd cementing  
plug, bridged with 1 sack of dry cement and 1/2 sack of hulls on fluid  
at 40', and cemented with 9 sacks to the base of the cellar. Rat and  
mouse holes bridged and cemented with 4 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving  
Well Plugging Supervisor

DATE 12/6/66

INV. NO. 4395-W