

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

JUL 19 1966

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Mace-Farha

Complete Address: 6410 Aberdeen, Wichita, Kansas

Lease Name Betzer Well No. # 1

Location E/2 E/2 NW Sec. 11 Twp. 31 Rge. 17 (E) (W) W

County Comanche Total Depth 5090'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: This hole was a wash down.

Plugging Contractor: Gabbert-Jones, Inc.

Address: 514 Orpheum Bldg., Wichita, Kansas License No.

Operation Completed: Hour 9:30PM Day 13th Month July Year 1966

The Above well was plugged as follows:

470' of 8 5/8" surface pipe, cement circulated. Fluid level in the
hole was at 400', 1st cementing plug, bridged with 2 sacks of dry
cement and 1/2 sack of hulls on fluid at 400', and cemented with 23
sacks. Hole was filled with drilling mud to 40', 2nd cementing plug,
bridged with 1 sack of dry cement and 1/2 sack of hulls on fluid at 40',
and cemented with 9 sacks to the base of the cellar. Rat hole bridged
and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 7/19/66
INV. NO. 3586-14