

KANSAS

Form CP-3
Rev. 6-26-62



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
NOV 27 1967
11-27-67
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Well Plugging Authority,
issued November 14, 1967.

Operator's Full Name Santa Fe Pipe & Supply, Inc.

Complete Address: Box 562, Great Bend, Kansas 67530

Lease Name R. R. Cook Well No. # 1

Location SE NW SE Sec. 18 Twp. 34 Rge. 12 (E) W

County Barber Total Depth 4850'

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Santa Fe Pipe & Supply, Inc.

Address: Box 562, Great Bend, Kansas 67530 License No. 574

Operation Completed: Hour 4:00PM Day 20th Month November Year 1967

The Above well was plugged as follows:

322' of 8 5/8" surface pipe, cement circulated. 4846' of 4 1/2" long string,
no record of cement. Top perforation 4811'. Bottom of the hole was sanded
to 4800', and cemented with 4 sacks, through the dump bailer. 3907' of
4 1/2" long string was recovered from the hole. Fluid in the hole was bailed
down to 300', bridge plug and rock bridge from 300' to 290', and cemented
with 25 sacks, with cement from 290' to 215'. Hole was filled with mud to
40', rock bridge from 40' to 30', and cemented with 10 sacks, with cement
from 30' to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 11-28-67

INV. NO. ~~11~~ 6748-W