

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

DEC 19 1963

12-19-63

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Santa Fe Pipe & Supply

Complete Address: P. O. Box 562, Great Bend, Kansas

Lease Name Christian Olson "C" Well No. # 1

Location SW NE SW Sec. 21 Twp. 34 Rge. 12 (E) (W) W

County Barber Total Depth 4793

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Ace Pipe Pulling Co.

Address: Box 304, Great Bend, Kansas License No.

Operation Completed: Hour 1:00PM Day 17th Month December Year 1963

The Above well was plugged as follows:

353' of 9 5/8" surface pipe, cemented with 300 sacks. 4792' of 5 1/2" long
string, cemented with 150 sacks. Plug back to 4760'. Top perferation
4700'. Sanded to 4680', and bottom cemented with 5 sacks. Fluid in hole
was bailed down to 280'. Plug with 10' rock bridge was set at 280',
cemented with 25 sacks. Hole was filled with mud to 35', 5' rock bridge,
cemented with 10 sacks to base cellar.

3600' of 5 1/2" long string was recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

DATE

12/19/63

INV. NO.

8314-U

Signed:

Archie Elving
Well Plugging Supervisor