

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

APR 15 1966  
4-15-66  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Petroleum, Inc.

Complete Address: R. R. # 2, Great Bend, Kansas

Lease Name Cook "F" Well No. # 1

Location C S/2 N/2 SE Sec. 21 Twp. 34 Rge. 12 (E) (W) W

County Barber Total Depth 4813'

Abandoned Oil Well Gas Well  Input Well SWD Well D & A

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Santa Fe Pipe & Supply, Inc.

Address: Box 562, Great Bend, Kansas License No. 574

Operation Completed: Hour 11:15AM Day 14th Month April Year 1966

The Above well was plugged as follows:

287' of 8 5/8" surface pipe, cemented with 175 sacks. 4810' of 4 1/2" long  
string, cemented with 100 sacks. Plug back T.D. 4752'. Top perferation  
4722'. Bottom of the hole was sandèd to 4560', and cemented with 3 sacks,  
through the dump bailer. Fluid in the hole was bailed down to 250', rock  
bridge from 250' to 240', and cemented with 25 sacks. Hole was filled  
with mud to 40', rock bridge from 40' to 30', and cemented with 10 sacks  
to the base of the cellar.

4285' of 4 1/2" long string was recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving  
Well Plugging Supervisor

DATE 4/15/66  
INV. NO. 3051-W