

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-035-22153-00-00  
Spot: SWNW Sec/Twnshp/Rge: 28-33S-4E  
3254 feet from S Section Line, 4522 feet from E Section Line  
Lease Name: RICHARDSON Well #: 2  
County: COWLEY Total Vertical Depth: 760 feet

Operator License No.: 33277  
Op Name: COOPER, ALBERT L. DBA COOPER SER  
Address: PO BOX 381  
WINFIELD, KS 67156

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	760		75 SX
SURF	7	211		200 SX

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/29/2014 8:00 AM  
Plug Co. License No.: 33277 Plug Co. Name: COOPER, ALBERT L. DBA COOPER SERVICE CO.  
Proposal Rcvd. from: ALBERT COOPER Company: COOPER SERVICE CO. Phone: (316) 204-0072

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: JEFF KLOCK Witness Type: PARTIAL  
Date/Time Plugging Completed: 01/29/2014 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/1" TBG @ 700' INSIDE 7" CASING, & RIH W/ 1/2" TBG @ 20' OUTSIDE 7" CASING. SWEDGED INTO 1/2" TBG, COPELAND ACID SERVICE, MIXED & PUMPED CEMENT TO SURFACE. CEMENT CIRCULATED. LAYED DOWN 1/2" TBG. SWEDGED INTO 1" TBG, COPELAND ACID SERVICE MIXED & PUMPED 85 SXS CLASS A COMMON TO SURFACE. CEMENT CIRCULATED. CEMENT TICKET # 40783.

Perfs:

Top	Bot	Thru	Comments
706	710	CSG	
672	679	CSG	

Remarks: COMPLIANCE /10 YR RULE

Plugged through: TBG

District: 02

Signed DUANE KRUEGER  
KCC WICHITA 3/13/14 (TECHNICIAN)

FEB 13 2014

RECEIVED