

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-015-19167-00-00  
Spot: NESWSWNE Sec/Twnshp/Rge: 3-25S-5E  
3272 feet from S Section Line, 2041 feet from E Section Line  
Lease Name: FRANK ROBISON EAST Well #: 27  
County: BUTLER Total Vertical Depth: 2412 feet

Operator License No.: 33192  
Op Name: CROWN ENERGY COMPANY  
Address: 1117 N.W. 24TH ST.  
OKLAHOMA CITY, OK 73106

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	7	2409		0 SX
SURF	12	0		0 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/15/2013 8:00 AM  
Plug Co. License No.: 31538 Plug Co. Name: BURKHOLDER, STEVE DBA HAD-A-CALL OIL  
Proposal Rcvd. from: DALLAS FLOWERS Company: CROWN ENERGY CO. Phone: (316) 321-0550

Proposed Plugging Method: SAND TO 2350 & 7 SXS, PERF 250 & CIRC

Plugging Proposal Received By: HUNTER CLARK WitnessType: PARTIAL  
Date/Time Plugging Completed: 10/17/2013 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH ON WIRELINE, TAGGED TB @ 2412', DUMPED SAND. 10-17-2013, TAGGED SAND @ 2350'. DUMP BAILED 7 SXS CEMENT ON TOP OF SAND, TAGGED CEMENT @ 2320'. RIH ON WIRELINE SET CIBP @ 300'. TESTED CASING @ 100#, HELD OK. RIH ON WIRELINE, SHOT SQUEEZE HOLES @ 255'-256' (4 HOLES). SWEDGED INTO 7" CASING, CONSOLIDATED OILWELL SERVICES ESTABLISHED CIRCULATION, MIXED & PUMPED 400 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 5:00 PM 10-17-2013. CONSOLAITED CEMENT TICKET #43172.

Perfs:

Top	Bot	Thru	Comments
2409	2412	OH	

Remarks: COMPLIANCE / 10 YR RULE

Plugged through: TBG

District: 02

Signed

DUANE KRUEGER

KCC WICHITA

(TECHNICIAN)

FEB 13 2014

RECEIVED