

** OK TO INV. AS PLUG DT'S. WIN 5 YR.*

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-205-25718-00-00 *BILLING CUTOFF.*
Spot: SWNWNENE Sec/Twnshp/Rge: 27-30S-15E
4833 feet from S Section Line, 1312 feet from E Section Line
Lease Name: WERTZ Well #: A3-27
County: WILSON Total Vertical Depth: 1447 feet

Operator License No.: 33074
Op Name: DART CHEROKEE BASIN OPERATING
Address: 600 DART RD PO BOX 177
MASON, MI 48854

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	1447		180 SX
SURF	8.625	22		5 SX
T1	2.375	1408		

Well Type: CM UIC Docket No: _____ Date/Time to Plug: 11/06/2012 12:00 AM
Plug Co. License No.: 5491 Plug Co. Name: W & W PRODUCTION COMPANY, GENERAL PARTNERSHIP
Proposal Rcvd. from: AARON HAMMERSCHMID Company: _____ Phone: (620) 331-7870

Proposed Plugging Method: TIH to 1432'. Set cmt plug fr 1432' - surf. Cut off csg. Restore loc.

Plugging Proposal Received By: ALAN DUNNING Witness Type: PARTIAL
Date/Time Plugging Completed: 11/06/2012 10:00 AM KCC Agent: ALAN DUNNING

Actual Plugging Report:

A cement string was run to 1430'. The well was then pumped full of cement from btm to top thru this cement string. A total of 113 sacks of portland cement were used to plug well. The well was cut off below plow depth and the location restored.

Perfs:

Top	Bot	Thru	Comments
1330	1331		
1213	1215		
1212	1214		
1067	1069		
1066	1068		
1009	1010		
1008	1009		
961	964		
848	849		
847	848		

RECEIVED

FEB 10 2014

KCC Chanute Dist. #3

AD

Remarks:

Plugged through: CSG

District: 03

Signed *Alan Dunning*
3/03/14 (TECHNICIAN)

KCC WICHITA

FEB 12 2014

RECEIVED