

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-019-19579-00-01
Spot: NWSWNWNW Sec/Twnshp/Rge: 15-34S-8E
4317 feet from S Section Line, 5028 feet from E Section Line
Lease Name: ZIMMERMAN Well #: B-2
County: CHAUTAUQUA Total Vertical Depth: 2166 feet

Operator License No.: 33809

Op Name: BELPORT OIL, INC.

Address: 1443 S NORFOLK AVE
TULSA, OK 74120

| String | Size | Depth (ft) | Pulled (ft) | Comment |
|--------|-------|------------|-------------|---------|
| PROD | 4.5 | 2160 | | 100 SX |
| SURF | 8.625 | 116 | | 0 SX |

Well Type: EOR

UIC Docket No: E18164.1

Date/Time to Plug:

Plug Co. License No.: 32884

Plug Co. Name: ELMORE'S, INC.

Proposal Recvd. from: GEORGE DAVENPORT

Company:

Phone: (918) 637-5476

Proposed This one well appears in the KGS database under two API numbers: 15-019-19579 and 15-019-00225. It actually is located
Plugging in the Sw Nw Nw as described under 15-019-00225, not the Sw Sw Nw as described under 15-019-19579.will
Method: spot/squeeze cement across Altamont & Pawnee perforations with top of plug above 1,910'; then 50' plug btwn KC and
Douglas and then 550' plug from 550' to surface. gel spacers will be pumped between plugs

Plugging Proposal Received By: DUANE SIMS

WitnessType: PARTIAL

Date/Time Plugging Completed: 12/12/2013 10:00 AM

KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 1" to 2050' gelled hole and spotted 30 sack plug. Pulled up to 1300' and spotted 10 sack plug. Pulled 1" and perforated casing at 550'. Ran 1" back in to 550' and circulated cement to surface inside and outside casing. 197 sacks of cement were used to plug this well.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 2068 | 2074 | | |
| 1962 | 1969 | | |

RECEIVED

FEB 11 2014

KCC Chanute Dist. #3

DS

Remarks: OPERATOR PLUGGED WELL BECAUSE IT WOULD NOT PASS MIT.

Plugged through: TBG

District: 03

KCC WICHITA

FEB 13 2014

RECEIVED

Signed

E. J. S.
02/28/14 (TECHNICIAN)
cc to WC02/28/14