

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-153-20979-00-00
Spot: S2SWSW Sec/Twnshp/Rge: 35-1S-36W
330 feet from S Section Line, 660 feet from W Section Line
Lease Name: KENNETH Well #: 1-35
County: RAWLINS Total Vertical Depth: 4740 feet

Operator License No.: 34318
Op Name: BEREXCO LLC
Address: 2020 N. BRAMBLEWOOD
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	309		225 sx

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 02/03/2014 12:00 AM
Plug Co. License No.: 34317 Plug Co. Name: BEREDCO LLC
Proposal Rcvd. from: MILO SALINIS Company: BEREDCO LLC Phone: (316) 833-2430

Proposed Plugging Method: Ordered 220 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: RAY DINKEL WitnessType: NONE
Date/Time Plugging Completed: 02/03/2014 10:30 AM KCC Agent: RAY DINKEL

Actual Plugging Report:

1st plug @3240 w/25 sx
2nd plug @2465 w/100 sx
3rd plug @360 w/40 sx
4th plug @40 w/10 sx

Rathole 30 sx Mousehole 15 sx

Perfs:

Remarks: ALLIED

Plugged through: DP

District: 04

Signed

Ray A. Dinkel
02/28/14

(TECHNICIAN)

KCC WICHITA

CM

FEB 19 2014

FEB 24 2014

Form CP-2/3

RECEIVED