

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-119-10156-00-01  
Spot: SEWSE Sec/Twnshp/Rge: 29-33S-29W  
1623 feet from S Section Line, 1643 feet from E Section Line  
Lease Name: HEINSON IDA K Well #: 5  
County: MEADE Total Vertical Depth: 6060 feet

Operator License No.: 33359  
Op Name: BKEP CRUDE LLC  
Address: 10750 MCCLARY RD PO BOX 1356  
DUMAS, TX 79029

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2700		WITH 4 SX CMT
CIBP		3030		
CIBP		5850		
PROD 7		6060	0	WITH 260 SX CMT
SURF	13.375	955		WITH 900 SX CMT

Well Type: SWD UIC Docket No: D17772.0 Date/Time to Plug: 02/13/2014 8:00 AM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: WILLIAM (BILL) HOLT Company: BKEP CRUDE Phone: (620) 544-5765

Proposed Plugging Method: SET CIBP @ 2700' WITH 4 SX CMT. PULL CASING & PLUG THROUGH TBG. PLUG AT 1500' WITH 30 SX GEL & 75 SX CMT. PLUG AT 980' WITH 100 SX CMT. PLUG AT 550' WITH 100 SX CMT. PLUG AT 60' WITH 50 SX CMT.

Plugging Proposal Received By: KEN JEHLIK Witness Type: PARTIAL  
Date/Time Plugging Completed: 02/13/2014 3:25 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 2700' WITH 4 SX CMT. 7" CASING WAS THEN PRESSURE TESTED & PROVED TO HAVE A SMALL LEAK (1.4 BPM @ 550#). PERFORATED @ 1500' & SET A CMT RETAINER @ 1000'. RAN TBG INTO THE CMT RETAINER & TOOK AN INJECTION RATE OF 2 BPM @ 200#. PUMPED 75 SX CMT & DISPLACED 50 SX CMT OUTSIDE OF THE CASING. PULLED TBG & PRESSURE TESTED THE 7" CASING TO 300# & HELD. PERFORATED @ 960'. TOOK AN INJECTION RATE OF 2 BPM @ 40#. BULLHEADED 75 SX CMT WITH 50# HULLS IN THE LAST 25 SX CMT. DISPLACED 50 SX CMT OUTSIDE THE CASING. PERFORATED @ 550' & CIRCULATED CMT TO SURFACE WITH 350 SX CMT. CIRCULATED 5 SX CMT TO PIT.

Perfs:

Top	Bot	Thru	Comments
5886	5890		
5825	5829		
2731	2934		

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

KCC WICHITA

FEB 19 2014

RECEIVED

District: 01

RECEIVED

FEB 14 2014

KCC DODGE CITY

Signed

(TECHNICIAN)