

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-169-20326-00-00  
Spot: NESESWSW Sec/Twnshp/Rge: 21-16S-1W  
530 feet from S Section Line, 1170 feet from W Section Line  
Lease Name: MAX REDDEN Well #: 1  
County: SALINE Total Vertical Depth: 2680 feet

Operator License No.: 34439  
Op Name: BOP WEST, LLC  
Address: PO BOX 129  
WOOSTER, OH 44691

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2600		
PROD	5.5	2678		130 SX
SURF	8.625	222		140 SX
T1	2.375	2662		

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/17/2013 12:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: GARY REED Company: QUALITY WELL SERVICE Phone: (316) 655-8775

Proposed Plugging Method: Dump bail 2sx cement on top of CIBP @ 2600'. Bridge casing @ 2035'. Sand back to 2010' to cover perms 2026'-2029'.  
Dump bail 2x cement plug. Rip casing above top of cement at 1650'. Pull casing to 272'. Pump 35 sx plug. Pull casng to 60'. Circulate cement to surface. Pull casing to surface. Top off with cement as needed.

Plugging Proposal Received By: JEFF KLOCK WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 09/18/2013 12:00 PM KCC Agent: HUNTER CLARK

Actual Plugging Report:

CIBP @ 2500' 2 SKS, CAP/ 2ND PLUG @ 2035' SET 5 SK CAP/CHECKED PLUG WITH SAND LINE PLUG @ 1978', RIPPED 5.5 @ 1500' PULLED 5.5 TO 212' CIRCULATED CEMENT TO SURFACE 110 SKS 60/40 4%. TOP OFF 15 SKS.

Perfs:

Top	Bot	Thru	Comments
2623	2628		
2618	2628		
2026	2029		

KCC WICHITA

FEB 19 2014

Remarks: TICKET #5974 QUALITY WELL SERVICE

RECEIVED

Plugged through: CSG

District: 02

Signed

*Hunter Clark*  
02/28/13  
(TECHNICIAN)

✓