

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-21891-00-00
Spot: S2N2S2NW Sec/Twnshp/Rge: 22-17S-11W
1815 feet from N Section Line, 1320 feet from W Section Line
Lease Name: ONNO SOEKEN Well #: 9
County: BARTON Total Vertical Depth: 3286 feet

Operator License No.: 31930
Op Name: BLUE RIDGE PETROLEUM CORPORATI
Address: PO BOX 1913
ENID, OK 73702

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3267		200 SX
SURF	8.625	651		350 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/29/2014 8:30 AM
Plug Co. License No.: 6123 Plug Co. Name: CHASE WELL SERVICE, INC.
Proposal Rcvd. from: RICK POPP Company: POPP OPERATING Phone: (620) 786-5514

Proposed
Plugging
Method:

Ordered 12 sx gel, 450 sx 60/40 pozmix 4% gel cement and 400 # hulls.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 01/29/2014 1:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perfs:

Perforated at 1450' and 630'.
Ran tubing to 3200' and pumped 12 sx gel followed by 50 sx cement w/100 # hulls. Pulled tubing to 1450' and pumped 100 sx cement w/200 # hulls. Pulled tubing to 650'. Circulated cement to surface on casing w/50 sx cement. Circulated cement to surface on surface pipe w/100 sx cement and 200 # hulls. Pulled tubing. Topped off w/10 sx cement.

GPS: 38.56008 -09853088

Remarks: QUALITY OILWELL CEMENTING

Plugged through: CSG

KCC WICHITA

FEB 11 2014

RECEIVED

District: 04

Signed

Bruce Rodie
01/28/14

(TECHNICIAN)

CM

FEB 06 2014