

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-24172-00-00
Spot: W2W2W2 Sec/Twnshp/Rge: 32-6S-19W
2640 feet from N Section Line, 330 feet from W Section Line
Lease Name: DETTMER-WILKENS Well #: 1-32
County: ROOKS Total Vertical Depth: 3630 feet

Operator License No.: 4629
Op Name: BRITO OIL COMPANY, INC.
Address: 1223 N. ROCK RD, BLDG I STE 100
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	219		150 sx

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 01/23/2014 12:00 AM
Plug Co. License No.: 33575 Plug Co. Name: WW DRILLING, LLC
Proposal Rcvd. from: KIRBY Company: WW DRILLING, LLC Phone: (785) 743-6774

Proposed Plugging Method: Ordered 255 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: MARVIN MILLS Witness Type: NONE
Date/Time Plugging Completed: 01/23/2014 9:00 AM KCC Agent: MARVIN MILLS

Actual Plugging Report:

1st plug @3516 w/50 sx
2nd plug @1630 w/25 sx
3rd plug @950 w/100 sx
4th plug @270 w/40 sx
5th plug @40 w/10 sx

Rathole 30 sx

Perfs:

Remarks: ALLIED

Plugged through: DP

KCC WICHITA

FEB 19 2014

RECEIVED

District: 04

Signed [Signature]
2/03/14 (TECHNICIAN)

CM