

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-165-22049-00-00
Spot: NWSESW Sec/Twnshp/Rge: 14-16S-20W
400 feet from S Section Line, 800 feet from W Section Line
Lease Name: DIXON ELLIOTT Well #: 1
County: RUSH Total Vertical Depth: 3126 feet

Operator License No.: 9860
Op Name: CASTLE RESOURCES, INC.
Address: BOX 87
SCHOENCHEN, KS 67667

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	219		WITH 150 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 01/27/2014 6:45 PM
Plug Co. License No.: 34743 Plug Co. Name: WHITE KNIGHT DRILLING LLC
Proposal Rcvd. from: TERRY AUSTIN Company: WHITE KNIGHT DRILLING LLC Phone: (785) 625-5155

Proposed
Plugging
Method:

TOP OF FISH @ 2218'. BIT STUCK AT 2800'. WILL BACK OFF PIPE & PLUG BACK TO DRILL SIDEKICK.

Plugging Proposal Received By: RICHARD LACEY
Date/Time Plugging Completed: 01/27/2014 6:45 PM

WitnessType: NONE
KCC Agent: RICHARD LACEY

Actual Plugging Report:

TOP OF FISH @ 2218'. BIT STUCK AT 2800'. WILL BACK OFF PIPE & PLUG BACK TO DRILL SIDEKICK. 1ST PLUG AT 1440' WITH 50 SX CMT. 2ND PLUG AT 970' WITH 100 SX CMT.

Perfs:

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY GLOBAL SCHIPPERS.

Plugged through: DP

District: 01

RECEIVED
FEB - 6 2014
KCC DODGE CITY

Signed

Richard W. Lacey
2/03/14

(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION
FEB 10 2014
CONSERVATION DIVISION
WICHITA, KS

AW