

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGIN  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-001-03231-00-00  
Spot: NWNWSENE Sec/Twnshp/Rge: 16-24S-18E  
3780 feet from S Section Line, 1220 feet from E Section Line  
Lease Name: CLINE Well #: RB26  
County: ALLEN Total Vertical Depth: 891 feet

Operator License No.: 5150  
Op Name: COLT ENERGY INC  
Address: PO BOX 388  
IOLA, KS 66749

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		873		
PROD 2		873		156 SX
SURF 7		19		4 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/31/2014 12:00 AM  
Plug Co. License No.: 5150 Plug Co. Name: COLT ENERGY INC  
Proposal Rcvd. from: REX ASHLOCK Company: \_\_\_\_\_ Phone: (620) 365-3111

Proposed Plugging Method: COMPANY UNIT RIH 1" TBG TO 873 TD. CONSOLIDATED OIL WELL SERVICES HOOK ON TO 1" BREAK CIRCULATION & PUMP 50' CEMENT PLUG ON BOTTOM. COMPANY UNIT PULLS 1" UP TO 500' CONSOLIDATED TO PUMP 50' CMT PLUG. COMPANY UNIT PULLS 1" UP TO 250' CONSOLIDATED TO PUMP CEMENT TO SURFACE. COMPANY UNIT PULL BALANCE OF 1" TBG CONSOLIDATED TOP WELL OFF.

Plugging Proposal Received By: \_\_\_\_\_ Witness Type: NONE  
Date/Time Plugging Completed: 01/31/2014 8:00 AM KCC Agent: RYAN DULING

Actual Plugging Report:

Ran 1" pipe to TD. Pumped and circulated cement through the 1" pipe from TD to surface. Pulled the 1" pipe out of the hole and topped the well off with cement. A total of 25 sacks of portland cement was reported used to plug this well.

Perfs:

Top	Bot	Thru	Comments
879	891		
RECEIVED FEB 18 2014 KCC Chanute Dist. #3 RD			

Remarks:

Plugged through: TBG

District: 03

Signed [Signature] (TECHNICIAN)  
+ 3/23/14

KCC WICHITA Form CP-2/3

FEB 20 2014

RECEIVED