

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-001-20047-00-00
Spot: SWNESWNE Sec/Twnshp/Rge: 16-24S-18E
3465 feet from S Section Line, 1695 feet from E Section-Line
Lease Name: CLINE Well #: RB30
County: ALLEN Total Vertical Depth: 901 feet

Operator License No.: 5150
Op Name: COLT ENERGY INC
Address: PO BOX 388
IOLA, KS 66749

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		886		
PROD 2		886		107 SX
SURF 7		18		0 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/31/2014 12:00 AM
Plug Co. License No.: 5150 Plug Co. Name: COLT ENERGY INC
Proposal Rcvd. from: REX ASHLOCK Company: _____ Phone: (620) 365-3111

Proposed Plugging Method: COMPANY UNIT RIH 1" TBG TO 886' CONSOLIDATED OIL WELL SERVICES HOOK ON TO 1" BREAK CIRCULATION & PUMP 50' CEMENT PLUG ON BOTTOM. COMPANY UNIT PULL 1" UP TO 500' CONSOLIDATED TO PUMP 50' CEMENT PLUG. COMPANY UNIT PULL 1" UP TO 250' CONSOLIDATED TO PUMP CEMENT TO SURFACE.. COMPANY UNIT PULL BALANCE OF 1" CONSOLIDATED TOP WELL OFF.

Plugging Proposal Received By: _____ WitnessType: NONE
Date/Time Plugging Completed: 01/31/2014 8:00 AM KCC Agent: RYAN DULING

Actual Plugging Report:

Ran 1" pipe to TD. Pumped and circulated cement through the 1" pipe from TD to surface. Pulled the 1" pipe out of the hole and topped the well off with cement. A total of 25 sacks of portland cement was reported used to plug this well.

Perfs:

Top	Bot	Thru	Comments
894	901		

RECEIVED
FEB 18 2014
KCC Chanute Dist. #3
RD

Remarks:

Plugged through: TBG

District: 03

Signed [Signature]
3/03/14 (TECHNICIAN)

KCC WICHITA

FEB 20 2014

RECEIVED