

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-207-28623-00-00
Spot: NWSENESE Sec/Twnshp/Rge: 20-23S-17E
3460 feet from N Section Line, 495 feet from E Section Line
Lease Name: GLEUE, E & I (855) Well #: C3
County: WOODSON Total Vertical Depth: 1252 feet

Operator License No.: 5150
Op Name: COLT ENERGY INC
Address: PO BOX 388
IOLA, KS 66749

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	40		

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 09/04/2013 12:00 AM
Plug Co. License No.: 5150 Plug Co. Name: COLT ENERGY INC
Proposal Rcvd. from: _____ Company: _____ Phone: _____

Proposed
Plugging
Method:

Plugging Proposal Received By: _____ WitnessType: NONE
Date/Time Plugging Completed: 09/04/2013 8:00 AM KCC Agent: RYAN DULING

Actual Plugging Report:

Mixed and pumped gel down drill stem at TD. Spotted 15 sacks of cement at TD. Pulled drill pipe up to 900'. Spotted 15 sacks of cement at 900'. Pulled up to 500'. Spotted 15 sacks of cement at 500'. Pulled drill stem up to 250'. Circulated cement from 250' to surface. Pulled the drill pipe out of the hole and topped the well off with cement. A total of 115 sacks of portland cement was reported used to plug this well.

Perfs:

RECEIVED
FEB 18 2014
KCC Chanute Dist. #3
RD

Remarks:

Plugged through: DP

District: 03

Signed [Signature]
3/03/14 (TECHNICIAN)

KCC WICHITA Form CP-2/3

FEB 20 2014

RECEIVED