

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGIN  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-001-23580-00-00  
Spot: SWNWSESW Sec/Twnshp/Rge: 9-24S-18E  
862 feet from S Section Line, 3827 feet from E Section Line  
Lease Name: KIRK Well #: RB-39  
County: ALLEN Total Vertical Depth: 950 feet

Operator License No.: 5150  
Op Name: COLT ENERGY INC  
Address: PO BOX 388  
IOLA, KS 66749

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2	920		0 SX
SURF	7	0		0 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/10/2013 12:00 AM  
Plug Co. License No.: 5150 Plug Co. Name: COLT ENERGY INC  
Proposal Rcvd. from: REX ASHLOCK Company: \_\_\_\_\_ Phone: (620) 365-3111

Proposed Plugging Method: SERVICE UNIT RIH W/1 1/4" TBG TO TD - CONSOLIDATED GEL HOLE UP- PUMP 150' CMT PLUG @TD PULL UP TBG TO 500' PMP 50' CMT PLUG. PULL UP TBG TO 250' PMP CMT TO SURFACE POOH TBG TOP OFF WELL. LATER GO BACK CUT SURFACE OFF PLOW DEPTH.

Plugging Proposal Received By: \_\_\_\_\_ Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 06/10/2013 8:00 AM KCC Agent: RYAN DULING

Actual Plugging Report:

Ran 1" pipe to TD. Circulated cement through the 1" pipe from TD to surface. Pulled the 1" pipe out of the well. Topped the well off with cement. A total of 29 sacks of portland cement was reported used to plug this well.

Perfs:

Top	Bot	Thru	Comments
923	950		

RECEIVED  
FEB 18 2014  
KCC Chanute Dist. #3  
RD

Remarks:

Plugged through: TBG

District: 03

Signed

  
3/03/14 (TECHNICIAN)

KCC WICHITA

Form CP-2/3

FEB 18 2014

RECEIVED