

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-001-26020-00-00
Spot: SESESESW Sec/Twnshp/Rge: 13-25S-19E
220 feet from S Section Line, 2860 feet from E Section Line
Lease Name: PALMER Well #: 7
County: ALLEN Total Vertical Depth: 886 feet

Operator License No.: 5150
Op Name: COLT ENERGY INC
Address: PO BOX 388
IOLA, KS 66749

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2.875	886		130 SX
SURF	7	50		0 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/30/2014 12:00 AM
Plug Co. License No.: 5150 Plug Co. Name: COLT ENERGY INC
Proposal Rcvd. from: RICK RICE Company: _____ Phone: (620) 365-3111

Proposed Plugging Method: IF CAN PMP WTR INTO WELL/FM, PMP AND FILL PROD CSG W/CMT, PRESS UP ON SAME AND SHUT WELL IN, IF CAN NOT PMP FLUID, RIH W/1" TBG AND FILL PROD CSG W/CMT, POOH 1" TBG TOP CSG OFF WITH CMT. PRESS UP AND SHUT WELL IN RETURN AT A LATER DATE AND CUT CSG OFF BELOW "PLOW DEPTH".

Plugging Proposal Received By: _____ Witness Type: PARTIAL
Date/Time Plugging Completed: 01/30/2014 8:00 AM KCC Agent: RYAN DULING

Actual Plugging Report:

Ran 1" pipe to 550'. Tried to wash down with no success. Pumped and circulated cement through the 1" pipe from TD to surface. Pulled the 1" pipe out of the hole and topped the well off with cement. Hooked onto the 2 7/8" casing and squeezed cement into the casing from surface and shut the well in at 500 psi. A total of 25 sacks of portland cement was reported used to plug this well.

Perfs:

Top	Bot	Thru	Comments
838	843		

RECEIVED
FEB 18 2014
KCC Chanute Dist. #3
RD

Remarks:

Plugged through: TBG

District: 03

Signed

[Handwritten Signature]
3/03/14 (TECHNICIAN)

KCC WICHITA

Form CP-2/3

FEB 20 2014

RECEIVED