

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGIN  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-001-26059-00-00  
Spot: SESESWSW Sec/Twnshp/Rge: 13-25S-19E  
220 feet from S Section Line, 4180 feet from E Section Line  
Lease Name: PALMER Well #: 9  
County: ALLEN Total Vertical Depth: 905 feet

Operator License No.: 5150  
Op Name: COLT ENERGY INC  
Address: PO BOX 388  
IOLA, KS 66749

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2.875	905		130 SX
SURF	7	50		0 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/30/2014 12:00 AM  
Plug Co. License No.: 5150 Plug Co. Name: COLT ENERGY INC  
Proposal Rcvd. from: RICK RICE Company: \_\_\_\_\_ Phone: (620) 365-3111

Proposed Plugging Method: IF CAN PMP WTR INTO WELL/FM, PMP AND FILL PROD CSG W/CMT, PRESS UP ON SAME AND SHUT WELL IN. IF CAN NOT PMP FLUID, RIH W/1"TBG TO BTM, PMP AND FILL PROD CSG W/CMT, POOH 1"TBG, TOP CSG OFF WITH CMT, PRESS UP AND SHUT WELL IN. RETURN AT A LATER DATE AND CUT CSG OFF BELOW "PLOW DEPTH".

Plugging Proposal Received By: \_\_\_\_\_ WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 01/30/2014 8:00 AM KCC Agent: RYAN DULING

Actual Plugging Report:

Ran 1" pipe to 650'. Tried to wash down with no success. Pumped and circulated cement through the 1" pipe from TD to surface. Pulled the 1" pipe out of the hole and topped the well off with cement. Hooked onto the 2 7/8" casing and squeezed cement into the casing from surface and shut the well in at 400 psi. A total of 40 sacks of portland cement was reported used to plug this well.

Perfs:

Top	Bot	Thru	Comments
852	871		


RECEIVED  
FEB 18 2014  
KCC Chanute Dist. #3  
RD

Remarks:

Plugged through: TBG

District: 03

Signed

  
3/03/14 (TECHNICIAN)

KCC WICHITA

Form CP-2/3

FEB 20 2014

RECEIVED