

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-001-22056-00-00

Spot: NWNWSE

Sec/Twnshp/Rge: 24-25S-19E

3740 feet from S Section Line, 3740 feet from E Section Line

Lease Name: WOLFE

Well #: RW-29

County: ALLEN

Total Vertical Depth: 917 feet

Operator License No.: 5150

Op Name: COLT ENERGY INC

Address: PO BOX 388

IOLA, KS 66749

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2	912		120 SX
SURF	7	50		0 SX

Well Type: EOR

UIC Docket No: E10334.82

Date/Time to Plug: 01/30/2014 12:00 AM

Plug Co. License No.: 5150

Plug Co. Name: COLT ENERGY INC

Proposal Rcvd. from: RICK RICE

Company:

Phone: (620) 365-3111

Proposed Plugging Method: IF CAN PMP WTR INTO WELL/FM, PMP AND FILL PROD CSG W/CMT, PRESSUP ON SAME AND SHUT WELL IN. IF CAN NOT PMP FLUID, RIH W/1" TBG TO BTM, PMP AND FILL PROD CSG W/CMT, POOH 1"TBG, TOP CSG OFF WITH CMT, PRESS UP AND SHUT WELL IN. RETURN AT A LATER DATE AND CUT CSG OFF BELOW "PLOW DEPTH".

Plugging Proposal Received By:

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 01/30/2014 8:00 AM

KCC Agent: RYAN DULING

Actual Plugging Report:

Ran 1" pipe to 875'. Pumped and circulated cement through the 1" pipe from TD to surface. Pulled the 1" pipe out of the hole and topped the well off with cement. A total of 25 sacks of portland cement was reported used to plug this well.

Perfs:

Top	Bot	Thru	Comments
861	871		
RECEIVED			
FEB 18 2014			
KCC Chanute Dist. #3			
RD			

Remarks:

Plugged through: TBG

District: 03

Signed

(TECHNICIAN)

KCC WICHITA

FEB 20 2014

RECEIVED

Form CP-2/3