

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-23827-00-00  
Spot: N2SESWNW Sec/Twnshp/Rge: 17-18S-13W  
3135 feet from S Section Line, 4290 feet from E Section Line  
Lease Name: YEAKLEY Well #: 2-B  
County: BARTON Total Vertical Depth: 3344 feet

Operator License No.: 3067  
Op Name: MOLITOR OIL, INC.  
Address: 9517 SW 80TH AVE  
SPIVEY, KS 67142

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3335		
SURF	8.625	738		

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/11/2014 11:00 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: STEVE MOLITOR Company: MOLITOR OIL Phone: (316) 650-8956

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement w/500 # hulls.

Plugging Proposal Received By: BRUCE RODIE Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 02/11/2014 2:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Sanded off bottom and topped with cement.  
Pulled stretch and could not cut casing. Perforated at 1450' and 710'. Ran tubing to 1706' and pumped 90 sx cement w/200 # hulls. Pulled tubing to 750'. Circulated cement to surface on casing with 120 sx cement and 300 # hulls. Pulled tubing. Tied to casing and topped off with 15 sx cement. Shut in pressure 500 psi. Tied to surface casing and pumed 5 sx cement to pressure up to 300 psi. Shut in.  
GPS: 38.49673 -098.78989

Perfs:

Remarks: COPELAND ACID AND CEMENTING

Plugged through: CSGTBG

KCC WICHITA  
FEB 28 2014  
RECEIVED

District: 04

Signed Bruce Rodie  
2/11/14 (TECHNICIAN) CM

FEB 18 2014