

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-03741-00-00
Spot: NWSENE Sec/Twnshp/Rge: 15-15S-15W
4325 feet from S Section Line, 365 feet from E Section Line
Lease Name: STEINERT (TWIN) Well #: 8
County: RUSSELL Total Vertical Depth: 3240 feet

Operator License No.: 3134
Op Name: MORRIS, TERRY E. DBA G L M COMPA
Address: PO BOX 193
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3239		
SURF	8.625	828		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/03/2014 11:30 AM
Plug Co. License No.: 34071 Plug Co. Name: PATRIOT WELL SERVICE, INC.
Proposal Rcvd. from: DAN WEINHOLD Company: G L M COMPANY Phone: (785) 483-1599

Proposed Plugging Method: Ordered 500 sx 60/40 sx pozmix 4% gel cement w/400 # hulls. Ordered 200 sx 60/40 pozmix 4% gel cement. Got out side casing. Trying to clean out and squeeze well at 2500'.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/03/2014 6:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Perforated at 825' and 1600'.
Ran tubing to 2500' and pumped 75 sx cement. Pulled tubing to 1600' and pumped 120 sx cement. Cement circulated out back side and fluid out braden head. Pumped a total of 425 sx cement at this point. POOH. Hooked to casing and pumped 180 sx cement. Cement circulated. Closed braden head valve and pressured casing to 170 psi and shut in.

GPS: 38.75212 -098.96469

Perfs:

Remarks: QUALITY CEMENTING TICKET # 7063

Plugged through: TBG

KCC WICHITA
FEB 11 2014
RECEIVED

District: 04

Signed Ray Dinkel (TECHNICIAN)
2/03/14

CM

FEB 06 2014