

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-36129-00-00
Spot: NENENW Sec/Twnshp/Rge: 23-12S-15W
4950 feet from S Section Line, 2970 feet from E Section Line
Lease Name: ELSASSER Well #: 2
County: RUSSELL Total Vertical Depth: 3160 feet

Operator License No.: 6246
Op Name: BENNETT & SCHULTE OIL CO., A GEN
Address: PO BOX 329
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3160		125 SX
SURF	8	200		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/19/2014 8:30 AM
Plug Co. License No.: 99977 Plug Co. Name: QUALITY OIL WELL CEMENTING
Proposal Rcvd. from: JOE ROTH Company: BENNETT AND SCHULTE OIL CO. Phone: (785) 623-3543

Proposed
Plugging
Method:

Ordered 205 sx 60/40 pozmix 4% gel cement, 500 # hulls and 8 sx gel. Lan- 2892' - 2910'

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/19/2014 1:10 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Perfs:

Pioneer Energy Services perforated at 1250', 782' and 375'. Ultimate Well Services ran in hole with tubing to 2825'. Quality rigged to tubing and mixed and pumped 8 sx gel followed by 50 sx cement w/200 # hulls mixed in. Pulled tubing to 1250'. Quality rigged to tubing and pumped 90 sx cement w/300 # hulls mixed in to circulate cement up 4 1/2" casing. Pulled tubing. Topped of 4 1/2" casing with 10 sx cement. Hole standing full. Rigged to 8 5/8" casing. Instant pressure.

GPS: 39.00097 -098.95648
4968' FSL 2970' FEL
NW NE NE NW


Remarks: QUALITY OILWELL CEMENTING TICKET # 461

Plugged through: TBG

KCC WICHITA
FEB 28 2014
RECEIVED

District: 04

Signed



(TECHNICIAN)

CM

FEB 24 2014