

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-171-21024-00-00
Spot: SWNESWSE Sec/Twnshp/Rge: 35-17S-31W
925 feet from S Section Line, 1674 feet from E Section Line
Lease Name: CRAIG Well #: 1-35
County: SCOTT Total Vertical Depth: 4695 feet

Operator License No.: 34318
Op Name: BEREXCO LLC
Address: 2020 N. BRAMBLEWOOD
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	424		WITH 250 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 02/13/2014 11:00 AM
Plug Co. License No.: 34318 Plug Co. Name: BEREXCO LLC
Proposal Rcvd. from: GILBERT Company: BEREXCO LLC Phone: (316) 265-3311

Proposed Plugging Method: 1ST PLUG AT 2280' WITH 50 SX CMT. 2ND PLUG AT 1550' WITH 80 SX CMT. 3RD PLUG AT 750' WITH 50 SX CMT. 4TH PLUG AT 450' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: DANIEL SELLERS WitnessType: NONE
Date/Time Plugging Completed: 02/13/2014 1:00 PM KCC Agent: DANIEL SELLERS

Actual Plugging Report:

1ST PLUG AT 2280' WITH 50 SX CMT. 2ND PLUG AT 1550' WITH 80 SX CMT. 3RD PLUG AT 750' WITH 50 SX CMT. 4TH PLUG AT 450' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Perfs:

KCC WICHITA
MAR 04 2014
RECEIVED

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY ALLIED.

Plugged through: DP

District: 01

Signed Daniel Sellers
3/07/14 (TECHNICIAN)

RECEIVED
FEB 27 2014

KCC DODGE CITY

Handwritten initials