

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-25877-00-00
Spot: N2SENENE Sec/Twnshp/Rge: 15-20S-11W
4575 feet from S Section Line, 330 feet from E Section Line
Lease Name: RINGERING Well #: 3-15
County: BARTON Total Vertical Depth: 3420 feet

Operator License No.: 6039
Op Name: L. D. DRILLING, INC.
Address: 7 SW 26TH AVE
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3416	2485	180 SX
SURF	8.625	343		350 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/14/2014 9:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: JAMIE Company: L D DRILLING Phone: (620) 562-0895

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/300 # hulls.

Plugging Proposal Received By: BRUCE RODIE Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/14/2014 12:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Sanded off bottom and bailed 5 sx cement on top. Cut casing at 2485' leaving 931' of casing in hole. Pulled casing to 1240' and pumped 125 sx cement w/200 # hulls. Pulled casing to 850' and pumped 50 sx cement w/100 # hulls. Pulled casing to 500' and pumped 40 sx cement w/100 # hulls. Pulled casing to 250' and pumped 100 sx cement. Circulated cement. POOH. Cellar full of cement.

GPS: 38.31717 -098.51808

Perfs:

Top	Bot	Thru	Comments
3327	3329		
3316	3319		

KCC WICHITA

FEB 28 2014

RECEIVED

Remarks: COPELAND ACID AND CEMENTING TICKET # 53234

Plugged through: CSG

District: 04

Signed Ray Dinkel
3/07/14 (TECHNICIAN)

CM

FEB 28 2014