

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-003-25885-00-00
Spot: NWNWNW Sec/Twnshp/Rge: 13-20S-20E
5132 feet from S Section Line, 4641 feet from E Section Line
Lease Name: ZASTROW Well #: 34-HP
County: ANDERSON Total Vertical Depth: 760 feet

Operator License No.: 33640
Op Name: HAAS PETROLEUM, LLC
Address: 11551 ASH ST., STE 205
LEAWOOD, KS 66211

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2.875	760		60 SX
SURF	7	20		2 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/16/2013 12:00 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: MARK HAAS Company: _____ Phone: (913) 499-8373

Proposed Plugging Method: Wash 1" tubing to TD - Spot 20 sacks (100' plug) @ TD. Pull 1" tubinh to 500'- Spot 10 sacks (50' Plug). Pull 1" tubing to 250' - fill to surface with cement. Total 60 sacks usede.

Plugging Proposal Received By: LEVI SHORT WitnessType: NONE
Date/Time Plugging Completed: 08/16/2013 12:00 AM KCC Agent: LEVI SHORT

Actual Plugging Report:

RUN 1-INCH TUBING TO 760 FEET INSIDE BOREHOLE AND PLACE 100 FOOT PLUG AT TD, 50 FOOT PLUG AT 500 FEET, THEN PLACE CEMENT PLUG FROM 250 FEET TO SURFACE. A TOTAL OF 60 SACKS OF CEMENT WAS USED TO PLUG THE WELL.

Perfs:

RECEIVED

FEB 12 2014

KCC Chanute Dist. #3


LS

Remarks:

Plugged through: OH

District: 03

Signed



(TECHNICIAN)

KCC WICHITA

Form CP-2/3

FEB 14 2014

RECEIVED