

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-203-20195-00-00  
Spot: NWNESESW Sec/Twnshp/Rge: 20-20S-35W  
1240 feet from S Section Line, 2295 feet from W Section Line  
Lease Name: BRACK Well #: 2  
County: WICHITA Total Vertical Depth: 5860 feet

Operator License No.: 34931  
Op Name: HEATH, MARK  
Address: 1421 S. COUNTY RD. 21  
LEOTI, KS 67861

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4470		WITH 2 SX CMT
PC		2365		NOT CEMENTED
PROD	4.5	4691	1016	WITH 150 SX CMT
SURF	8.625	225		WITH 165 SX CMT

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/29/2014 8:30 AM  
Plug Co. License No.: 32810 Plug Co. Name: PROFESSIONAL PULLING SERVICES LLC  
Proposal Rcvd. from: JEFF PFANNENSTIEL Company: PROFESSIONAL PULLING SERVIC Phone: (785) 628-7443

Proposed Plugging Method: CIBP @ 4470' & 2 SX CMT OR SAND TO 4470' & 4 SX CMT. PLUG AT 2283' WITH 20 SX GEL & 50 SX CMT. PLUG AT 1200' WITH 80 SX CMT. PLUG AT 600' WITH 50 SX CMT. PLUG AT 250' WITH 40 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 01/29/2014 5:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 4470' WITH 2 SX CMT. PERFORATE @ 2285'. INJECTION RATE 2 1/2 BPM @ 500#. PUMP 50 SX CMT WITH 50# HULLS IN THE LAST 25 SX CMT. DISPLACED 25 SX CMT OUT PERFS. SHOOT CASING OFF AT 1016' & POOH. RUN TBG TO 1200'. SPOT 17 SX GEL & 80 SX CMT. FULL CIRCULATION. PLUG AT 600' WITH 50 SX CMT. PLUG AT 250' WITH 40 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4520	4524		

RECEIVED  
KANSAS CORPORATION COMMISSION

FEB 10 2014

CONSERVATION DIVISION  
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

Signed

*Ken Jehlik*  
3/06/14

(TECHNICIAN)

RECEIVED

FEB - 3 2014

KCC DODGE CITY

*mark*