

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-081-22044-00-00
Spot: SESENWSW Sec/Twnshp/Rge: 17-30S-31W
1632 feet from S Section Line, 1008 feet from W Section Line
Lease Name: HAMMER "A" Well #: 1-17
County: HASKELL Total Vertical Depth: 5675 feet

Operator License No.: 5003
Op Name: MCCOY PETROLEUM CORPORATION
Address: 8080 E CENTRAL STE 300
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	833		

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 01/29/2014 10:45 PM
Plug Co. License No.: 5142 Plug Co. Name: STERLING DRILLING COMPANY
Proposal Revd. from: UVALDO Company: STERLING DRILLING COMPANY Phone: (620) 672-9508

Proposed Plugging Method: 1ST PLUG AT 1790' WITH 50 SX CMT. 2ND PLUG AT 840' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT. 4TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 5TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: NONE
Date/Time Plugging Completed: 01/30/2014 12:45 AM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

Perfs:

CMT FELL TO 100' ON SURFACE PIPE. RAN 1" & TOPPED OFF WITH 110 SX CMT 1ST PLUG AT 1790' WITH 50 SX CMT. 2ND PLUG AT 840' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT. 4TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 5TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY ALLIED.

Plugged through: DP

District: 01

Signed Michael J. Maier
3/07/14 (TECHNICIAN)

RECEIVED
JAN 30 2014
KCC DODGE CITY

KCC WICHITA
FEB 18 2014
RECEIVED

Form CP-2/3

mg