

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-019-26932-00-00
Spot: NWSESESW Sec/Twnshp/Rge: 8-33S-12E
346 feet from S Section Line, 3086 feet from E Section Line
Lease Name: LANE Well #: 14-8
County: CHAUTAUQUA Total Vertical Depth: 1688 feet

Operator License No.: 34779
Op Name: LR ENERGY, INC.
Address: 8150 N. CENTRAL EXPY, STE 1605
DALLAS, TX 75206

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	1676		250 SX
SURF	8.625	42		8 SX
T1	2.375	1662		

Well Type: CM UIC Docket No: _____ Date/Time to Plug: 10/17/2013 12:00 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: JACOB MCCLAIN Company: _____ Phone: (620) 627-2499

Proposed Plugging Method: Spot 100' plug on bottom. Pump gel spacer to 1396'. Pump 100' cement plug to cover remaining perforations. Pump gel to 800'. Spot 50' plug above KC Lime. Pump gel to 275'. Pump 275' to surface with cement.

Plugging Proposal Received By: DUANE SIMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/17/2013 12:00 PM KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 2" to 1675' gelled hole and spotted 35 sack plug to cover all perforations. Pulled up to 800' and spotted 5 sack plug. Pulled up to 293' and circulated cement to surface. Pulled 2" and topped well off. A total of 75 sacks of 60/40 pozmix was used to plug this well.

Perfs:

Top	Bot	Thru	Comments
1633	1636		RIVERTON
1393	1396		CROWEBURG
1376	1377		BEVIER
1347	1350		MULKY
1327	1330		SUMMIT

RECEIVED

FEB 11 2014

KCC Chanute Dist. #3

DS

Remarks: WELL WAS PLUGGED DUE TO COMPLAINT FROM LANDOWNER ABOUT OPERATOR HAVING NO LEASE.

Plugged through: TBG

District: 03

Signed [Signature]
KCC WICHITA (TECHNICIAN)

FEB 13 2014

RECEIVED