

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGIN  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-049-22388-00-01  
Spot: NENENESE Sec/Twnshp/Rge: 30-29S-10E  
2572 feet from S Section Line, 307 feet from E Section Line  
Lease Name: PERKINS WDW Well #: 9-30-29-10  
County: ELK Total Vertical Depth: 2846 feet

Operator License No.: 34779  
Op Name: LR ENERGY, INC.  
Address: 8150 N. CENTRAL EXPY, STE 1605  
DALLAS, TX 75206

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		2555		
PROD	7	2558		575 SX
SURF	10.75	469		450 SX
T1	2.875	2501		

Well Type: SWD UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/26/2013 12:00 AM  
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC  
Proposal Rcvd. from: JACOB MCCLAIN Company: \_\_\_\_\_ Phone: (620) 627-2499

Proposed Plugging Method: Spot 50' cement plug on bottom at 2555'. Pump gel spacer to 2495'. Pump 50' cement plug over perforations. Pump gel spacer to 1400'. Spot 50' plug over KC Lime. Pump gel spacer to 500'. Pump 500' cement to surface.

Plugging Proposal Received By: DUANE SIMS WitnessType: NONE  
Date/Time Plugging Completed: 11/26/2013 12:00 AM KCC Agent: DUANE SIMS

Actual Plugging Report:

Hooked onto 7" casing and squeezed 450 sacks of cement down casing. Let set for 15 minutes and topped well off.

Perfs:

Top	Bot	Thru	Comments
2558	2846		OPEN HOLE
2487	2495		CHATTANOOGA S

RECEIVED

FEB 11 2014

KCC Chanute Dist. #3

DS

Remarks:

Plugged through: CSG

District: 03

KCC WICHITA

FEB 13 2014

RECEIVED

Signed

*Duane A Sims*

(TECHNICIAN)

*cc to WCC 02/17/14*