

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-07380-00-00
Spot: NENENW Sec/Twnshp/Rge: 17-18S-13W
330 feet from N Section Line, 2310 feet from W Section Line
Lease Name: YEAKLEY Well #: 4
County: BARTON Total Vertical Depth: 3299 feet

Operator License No.: 3067
Op Name: MOLITOR OIL, INC.
Address: 9517 SW 80TH AVE
SPIVEY, KS 67142

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5	3294		100 SX
SURF	8	750		375 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/10/2014 11:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: STEVE MOLITOR Company: MOLITOR OIL Phone: (316) 650-8956

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement w/500 # hulls.

Plugging Proposal Received By: BRUCE RODIE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/10/2014 2:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Sanded off bottom and topped with cement.
Pulled stretch and could not cut casing. Perforated at 1450' and 730'. Ran tubing to 1706' and pumped 90 sx cement w/200 # hulls. Pulled tubing to 750'. Circulated cement to surface on casing with 150 sx cement and 300 # hulls. Shut in casing and circulated cement to surface on surface pipe with 125 sx cement. Pulled tubing and hole stayed full.
GPS: 38.49167 -098.78563

Perfs:

Remarks: COPELAND ACID AND CEMENTING
Plugged through: CSG

KCC WICHITA
FEB 28 2014
RECEIVED

District: 04

Signed Bruce Rodie
2/10/14 (TECHNICIAN) CM

FEB 13 2014