

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-23314-00-00
Spot: NESENWNW Sec/Twnshp/Rge: 27-34S-13W
930 feet from N Section Line, 1263 feet from W Section Line
Lease Name: STERLING Well #: 1-27
County: BARBER Total Vertical Depth: 4990 feet

Operator License No.: 3080
Op Name: JACK EXPLORATION, INC.
Address: 812 W 11TH ST PO BOX 1279
SULPHUR, OK 73086

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4675		WITH 2 SX CMT
COND	20	55		5.5 YDS. GROUT
PROD	4.5	4994	2600	WITH 250 SX CMT
SURF	13.375	236		WITH 240 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 02/10/2014 10:00 AM
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION
Proposal Rcvd. from: MARK MORGENSTERN Company: CLARKE CORPORATION Phone: (620) 886-5665

Proposed Plugging Method: SET CIBP @ 4680' WITH 2 SX CMT. PLUG AT 600' WITH 20 SX GEL & 50 SX CMT. PLUG AT 260' WITH 125 SX CMT. PLUG AT 60' WITH 50 SX CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: NONE
Date/Time Plugging Completed: 02/10/2014 12:00 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SET CIBP @ 4675' WITH 2 SX CMT. 1ST PLUG AT 600' WITH 20 SX GEL & 50 SX CMT. 2ND PLUG AT 260' WITH 125 SX CMT. 3RD PLUG AT 60' WITH 50 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4860	4870		
4790	4810		
4736	4760		

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: CSG

District: 01

RECEIVED
FEB 11 2014
KCC DODGE CITY

Signed

Richard M. Lacey
3/06/14

(TECHNICIAN)

KCC WICHITA

FEB 12 2014

RECEIVED

Form CP-2/3

AMF