

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGIN  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-019-24894-00-00  
Spot: SESESENW Sec/Twnshp/Rge: 34-34S-10E  
2860 feet from S Section Line, 2860 feet from E Section Line  
Lease Name: EDWARDS Well #: 2  
County: CHAUTAUQUA Total Vertical Depth: 1472 feet

Operator License No.: 31302  
Op Name: JONES & BUCK DEVELOPMENT, LLC  
Address: PO BOX 68  
SEDAN, KS 67361

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	6.875	1470		0 SX
SURF	12	40		0 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/27/2013 12:00 AM  
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.  
Proposal Revd. from: P J BUCK Company: \_\_\_\_\_ Phone: (620) 725-3636

Proposed Plugging Method: Surface cement and production casing cement unknown. Run 1" to TD. Gel hole. Spot 50' plug of cement on bottom. Pull out and perforate at 800' and 500'. Run 1" back in and spot 50' plug of cement at 800'. Pull up to 500' and cement to surface.

Plugging Proposal Received By: DUANE SIMS Witness Type: NONE  
Date/Time Plugging Completed: 11/29/2013 12:00 PM KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 1" to 1200' gelled hole and spotted 20 sack plug. Pulled 1" and perforated casing at 700' and 550'. Ran 1" back into 700' and spotted 20 sack plug. Pulled up to 550' and circulated cement to surface. Pulled 1" and topped well off. A total of 165 sacks of cement were used to plug this well.

Perfs:

RECEIVED  
FEB 18 2014  
KCC Chanute Dist. #3

DS

Remarks:

Plugged through: TBG

District: 03

Signed

Duane A Sims  
3/05/14  
(TECHNICIAN)

KCC WICHITA

FEB 20 2014

RECEIVED