

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-019-40388-00-00
Spot: SWNWNWNE Sec/Twnshp/Rge: 22-34S-12E
4635 feet from S Section Line, 2518 feet from E Section Line
Lease Name: HILLS Well #: 9
County: CHAUTAUQUA Total Vertical Depth: 940 feet

Operator License No.: 32255
Op Name: KANSAS ENERGY COMPANY, L.L.C.
Address: BOX 68
SEDAN, KS 67361

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	1150		0 SX
SURF	10	20		0 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/23/2014 12:00 AM
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.
Proposal Rcvd. from: P.J. BUCK Company: _____ Phone: (620) 725-3636

Proposed Plugging Method: Surface and production cement unknown. Run 1" to TD. Gel hole. Spot 50' plug of cement on bottom. Pull out and perforate at 700' and 350'. Run 1" back in and spot 50' of cement at 700'. Pull up to 350' and cement to surface.

Plugging Proposal Received By: DUANE SIMS Witness Type: PARTIAL
Date/Time Plugging Completed: 01/24/2014 12:00 PM KCC Agent: DUANE SIMS

Actual Plugging Report:
Ran 1" to 1000' gelled hole and spotted 20 sack plug. Pulled 1" and perforated casing at 700' and 350'. Ran 1" back into 700' and spotted 15 sack plug. Pulled up to 350' and circulated cement to surface. Pulled 1" and topped well off. A total of 135 sacks of cement were used to plug this well.

Perfs:

RECEIVED
FEB 18 2014
KCC Chanute Dist. #3
DS

Remarks:
Plugged through: TBG

District: 03

Signed [Signature]
3/05/14 (TECHNICIAN)

KCC WICHITA Form CP-2/3
FEB 20 2014
RECEIVED