

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGIN  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-019-40438-00-00  
Spot: SWNENENE Sec/Twnshp/Rge: 34-34S-10E  
4649 feet from S Section Line, 643 feet from E Section Line  
Lease Name: KEENAN Well #: 19  
County: CHAUTAUQUA Total Vertical Depth: 1414 feet

Operator License No.: 32255  
Op Name: KANSAS ENERGY COMPANY, L.L.C.  
Address: BOX 68  
SEDAN, KS 67361

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5	1230		0 SX
SURF	10.625	8		0 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/02/2013 12:00 AM  
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.  
Proposal Rcvd. from: P.J. BUCK Company: \_\_\_\_\_ Phone: (620) 725-3636

Proposed Plugging Method: Surface cement and production casing cement unknown. Run 1" to TD. Gel hole. Spot 50' plug of cement on bottom. Pull out and perforate at 800' and 500'. Run 1" back in and spot 50' plug of cement at 800'. Pull up to 500' and cement to surface.

Plugging Proposal Received By: DUANE SIMS Witness Type: NONE  
Date/Time Plugging Completed: 10/03/2013 12:00 PM KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 1" to 1300' gelled hole and spotted 20 sack plug. Pulled 1" and perforated casing at 900' and 550'. Ran 1" back into 900' and spotted 15 sack plug. Pulled up to 550' and circulated cement to surface. Pulled 1" and topped well off. A total of 150 sacks of cement were used to plug this well.

Perfs:

RECEIVED

FEB 18 2014

KCC Chanute Dist. #3


DS

Remarks:

Plugged through: TBG

District: 03

Signed

  
8/05/14 (TECHNICIAN)

KCC WICHITA

Form CP-2/3

FEB 20 2014

RECEIVED