

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGIN  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-125-24988-00-01  
Spot: SWNWNENW Sec/Twnshp/Rge: 9-33S-14E  
4675 feet from S Section Line, 3779 feet from E Section Line  
Lease Name: WRIGHT IDA Well #: 2  
County: MONTGOMERY Total Vertical Depth: 940 feet

Operator License No.: 32255  
Op Name: KANSAS ENERGY COMPANY, L.L.C.  
Address: BOX 68  
SEDAN, KS 67361

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	1220		127 SX
SURF	7	50		0 SX

Well Type: EOR UIC Docket No: E21112.1 Date/Time to Plug:  
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.  
Proposal Rcvd. from: P.J. BUCK Company: Phone: (620) 725-3636

Proposed Plugging Method: Surface cement unknown. Run 1" to TD. Gel hole. Spot 50' plug of cement on bottom. Spot 50' of cement at 700'. Pull up to 350' and cement to surface.

Plugging Proposal Received By: DUANE SIMS Witness Type: PARTIAL  
Date/Time Plugging Completed: 01/17/2014 10:00 AM KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 1" to 1000' gelled hole and spotted 10 sack plug. Pulled up to 600' and spotted 10 sack plug. Pulled up to 225' and circulated cement to surface. Pulled 1" and topped well off. A total of 50 sacks of cement were used to plug this well.

Perfs:

RECEIVED

FEB 11 2014

KCC Chanute Dist. #3

DS

Remarks: WELL WAS PLUGGED DUE TO FAILED MIT

Plugged through: TBG

District: 03

KCC WICHITA

FEB 13 2014

RECEIVED

Signed

*[Signature]*  
8/05/14 (TECHNICIAN)  
cc to MIC 02/17/14