

Phone 913-23-2621, Russell, KS
Phone 316-793-5861, Great Bend, KS

Phone 913-825-5816, Hays, KS
Phone 913-672-3471, Oakley, KS

Phone 316-886-5828, Medicine Lodge, KS
Phone 913-798-3843, Ness City, KS

ALLIED CEMENTING CO., INC.

6430

Home Office P. O. Box 31

Russell, Kansas 67668

New

Date	7/7/94	Sec.	16	Twp.	34s	Range	10W	Called Out	2:00 PM	On Location	3:30 PM	Job Start	7:00 PM	Finish	8:00 PM
Case	Diel	Well No.	1-16	Location	HAZELTON 1/4 SW 1/4 E/S			County	Barber	State	KS				

Contractor	Eagle Drilling		
Type Job	CMT 8 3/4 SURFACE CSG		
Hole Size	12 1/4	T.D.	312
Case	8 3/4 24"	Depth	313
Tbg. Size		Depth	
Drill Pipe		Depth	
Tool		Depth	
Cement Left in Cas.	25	Shoe Joint	25
Press Max.	500	Minimum	50
Meas Line	-	Displace	18.5
Perf.			

EQUIPMENT

No.	Cementer	Max Ball
Pumpark 234	Helper	JUSTIN HART
No.	Cementer	
Pumpark	Helper	
238	Driver	JOHN KELLEY
Bulktrk	Driver	

DEPTH of Job	313'	
References:		
313 FT	Pump Charge	435.07
25 Mi	Mileage	56.25
1 Ea	8 3/4 Wooden Plug	42.00
	Sub Total	
	Tax	
	Total	533.32

Remarks: CMT 8 3/4 SURFACE CSG WITH 115 SKS
'5/35' 67% GEL 37% CACL² 1/4" FLO-SEAL + 100 SKS
CLASS A + 27% GEL 37% CACL² DROP PLUG
Displace 18.5 MBL Land Plug Close in
Head CMT Did Circulate

Owner	To Allied Cementing Co., Inc. You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as listed.
Charge To	JACK EXPLORATION, INC.
Street	P.O. Box 1279
City	SULPHUR State OKLA 73086
The above was done to satisfaction and supervision of owner agent or contractor.	
Purchase Order No.	
X	K.O. Stained

CEMENT

Amount 115 SKS 65/75' 67% GEL 37% CACL² 1/4" FLO-SEAL
Ordered 100 SKS CLASS A + 27% GEL 37% CACL²

Consisting of		
Common	175	1006.25
Poz. Mix	40	120.00
Gel.	8	72.00
Chloride	7	175.00
Quickest		
FLO-SEAL	29 #	31.90

Handling	215	215.00
Mileage	215	215.00
Sub Total		
Total		1835.15

Flowing Equipment	
1- 8 3/4 Sawtooth Shear	240.00
1- 8 3/4 Baffle	105.00
	345.00
	#2713.47
Less	542.69
Net, 30 Days #	2170.78

15-007-22446-00-00
ORIGINAL

Jack Exploration, Inc. Diel 1-16

Drill Stem Tests

DST #1 4643-4700; 30", 60", 60", 120"
GTS 4" Max Flow 627 mcf; Rec 140' GCM,
HP 2226# & 2170# FP 145-123/112-89
SIPs 1779 - 1611

DST #2 4700-4735; 30", 60", 30", 60"
Rec 70' SOCM, 60' MSW HP 2226# - 2204#
FP 58-58/112-112 SIPs 1834 - 1812

RECEIVED
STATE CORPORATION COMMISSION

AUG 16 1994

CONSERVATION DIVISION
WICHITA, KANSAS

STATE CORPORATION COMMISSION OF KANSAS
OIL & GAS CONSERVATION DIVISION
WELL COMPLETION FORM
ACQ-1 WELL HISTORY
DESCRIPTION OF WELL AND LEASE

Operator: License # 03080

Name: Jack Exploration, Inc.

Address P.O. Box 1279

Sulphur, OK 73086

City/State/Zip _____

Purchaser: NA

Operator Contact Person: James R. Jack

Phone (405) 622-2310

Contractor: Name: Eagle Drilling Co., Inc.

License: 5380

Wellsite Geologist: Mike Pollak

Designate Type of Completion
 New Well Re-Entry Workover

Oil SWD SIOV Temp. Abd.
 Gas ENHR SIGW
 Dry Other (Core, WSW, Expl., Cathodic, etc)

If Workover/Re-Entry: old well info as follows:

Operator: _____

Well Name: _____

Comp. Date _____ Old Total Depth _____

Deepening Re-perf. Conv. to Inj/SWD
 Plug Back PBTB
 Commingled Docket No. _____
 Dual Completion Docket No. _____
 Other (SWD or Inj?) Docket No. _____

11/16/94 11/21/94 11/22/94
Spud Date Date Reached TD Completion Date

API NO. 15- 00722464 - ORIGINAL

County Barber

C S/2 SE Sec. 16 Twp. 34S Rge. 10 ^E _W

330 Feet from N (circle one) Line of Section

1320 Feet from W (circle one) Line of Section

Footages Calculated from Nearest Outside Section Corner:
NE, SE, NW or SW (circle one)

Lease Name Schrock Well # 1-16

Field Name WC

Producing Formation NA

Elevation: Ground 1354 KB 1367

Total Depth 4255 PBTB _____

Amount of Surface Pipe Set and Cemented at 228 Feet

Multiple Stage Cementing Collar Used? Yes No

If yes, show depth set _____ Feet

If Alternate II completion, cement circulated from _____

feet depth to _____ w/ _____ sx cat.

Drilling Fluid Management Plan D&A 896 10-17-95
(Data must be collected from the Reserve Pit)

Chloride content: 25,000 ppm Fluid volume 1000 bbls

Dewatering method Used Evaporation

Location of fluid disposal if hauled offsite: _____

Operator Name Clarke Corporation

Lease Name S. McQuire License No. 122270

NW Quarter Sec. 29 Twp. 32 S Rng. 10 ^E _W

County Barber Docket No. CD 11804

INSTRUCTIONS: An original and two copies of this form shall be filed with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within 120 days of the spud date, recompletion, workover or conversion of a well. Rule 82-3-130, 82-3-106 and 82-3-107 apply. Information on side two of this form will be held confidential for a period of 12 months if requested in writing and submitted with the form (see rule 82-3-107 for confidentiality in excess of 12 months). One copy of all wireline logs and geologist well report shall be attached with this form. ALL CEMENTING TICKETS MUST BE ATTACHED. Submit CP-4 form with all plugged wells. Submit CP-111 form with all temporarily abandoned wells.

All requirements of the statutes, rules and regulations promulgated to regulate the oil and gas industry have been fully complied with and the statements herein are complete and correct to the best of my knowledge.

Signature James R. Jack
Title President Date 12-9-94

Subscribed and sworn to before me this 9th day of December, 1994.

Notary Public Susan L. Watterson

Date Commission Expires July 22, 1997

DEC 7 8 30 AM 1994
K.C.C. OFFICE USE ONLY
F Letter of Confidentiality Attached
C Wireline Log Received
C Geologist Report Received
Distribution
 KCC SWD/Rep NGPA
 KGS Plug Other
(Specify)

ALLIED CEMENTING CO., INC.

15-007-22464-0000

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

ORIGINAL

SERVICE POINT:
Medicine Lodge

DATE <u>11/22/94</u>	SEC. <u>16</u>	TWP. <u>34s</u>	RANGE <u>10W</u>	CALLED OUT <u>12:30 AM</u>	ON LOCATION <u>1:30 AM</u>	JOB START <u>3:00 AM</u>	JOB FINISH <u>5:00 AM</u>
LEASE <u>Schrock</u>	WELL# <u>1-16</u>	LOCATION <u>Hazleton 1/2 S 1/4 W N/5</u>			COUNTY <u>Barber</u>	STATE <u>KS</u>	

OLD OR NEW (Circle one)

CONTRACTOR <u>Eagle</u>	OWNER <u>Same</u>
TYPE OF JOB <u>Rotary Plug</u>	CEMENT
HOLE SIZE <u>7 7/8</u>	T.D. <u>4250</u>
CASING SIZE <u>8 7/8 24#</u>	DEPTH <u>228</u>
TUBING SIZE	DEPTH
DRILL PIPE <u>4 1/2 16.60"</u>	DEPTH <u>650</u>
TOOL	DEPTH
PRES. MAX <u>175</u>	MINIMUM <u>50</u>
MEAS. LINE	SHOE JOINT
CEMENT LEFT IN CSG.	
PERFS.	

AMOUNT ORDERED	<u>135 sks 60/40 1.6 gel</u>		
COMMON	<u>81</u>	@	<u>5.75</u> <u>465.75</u>
POZMIX	<u>54</u>	@	<u>3.00</u> <u>162.00</u>
GEL	<u>7</u>	@	<u>9.00</u> <u>63.00</u>
CHLORIDE		@	
		@	
		@	
		@	
		@	
		@	
HANDLING	<u>135</u>	@	<u>1.00</u> <u>135.00</u>
MILEAGE	<u>135 x 25</u>		<u>.04</u> <u>135.00</u>

EQUIPMENT

PUMP TRUCK	CEMENTER <u>Max Hall</u>
# <u>266</u>	HELPER <u>Justin Hart</u>
BULK TRUCK	
# <u>227</u>	DRIVER <u>John Kelley</u>
BULK TRUCK	
#	DRIVER

TOTAL \$960.75

REMARKS:

SERVICE

Plug well by spotting plug thru
Drill Pipe 50sk @ 650 50sk @ 250
10sk @ 40' 10sk Mouse Hole 15sk
Rat hole

DEPTH OF JOB	<u>650'</u>		
PUMP TRUCK CHARGE			<u>430.00</u>
EXTRA FOOTAGE		@	
MILEAGE	<u>25M</u>	@	<u>2.25</u> <u>56.25</u>
PLUG		@	
		@	
		@	

TOTAL \$486.25

CHARGE TO: Jack Exploration Inc
STREET Box 1279
CITY Sulphur STATE OKLA. ZIP 73086

FLOAT EQUIPMENT

	@	
	@	
	@	
	@	
	@	

TOTAL

TAX	<u>- 0 -</u>
TOTAL CHARGE	<u>\$1447.00</u>
DISCOUNT	<u>\$217.05</u> IF PAID IN 30 DAYS

To Allied Cementing Co., Inc.
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

SIGNATURE Kenneth L. McNeil