

Copy of letter to Dept.

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
245 North Water
WICHITA, KANSAS 67202

Rev. 6-3-74
FORM (P-1)

WELL PLUGGING APPLICATION FORM
File One Copy

API Number 15 - 135 - 22,181-00 W (of this well)

Lease Owner Voyager Petroleum, Inc. (303) 629-1447

Address 110 16th Street, Denver, CO 80202

Lease (Farm Name) McCormick Well No. #34-14

Well Location C SE SW Sec. 34 Twp. 17S Rge. 21W ~~(21)~~ ~~(22)~~

County Ness Total Depth 4325' Field Name McCormick Field extension

Oil Well Gas Well Input Well SWD Well Rotary D & A

Well Log attached with this application as required _____

Date and hour plugging is desired to begin At discretion of plugging agent and contractor to be accomplished by 2/01/84.

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-128 OF THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

Name of company representative authorized to be in charge of plugging operations:

Layle L. Robb (303) 629-1447 Address 110 16th Street, Denver, CO 80202

Plugging Contractor Clarke Corporation License No. 583

Address 107 W. Fowler, Medicine Lodge, Kansas 67104 (316) 886-5665

Invoice covering assessment for plugging this well should be sent to:

Name Voyager Petroleum, Inc. - Attention: Layle L. Robb

Address 110 16th Street, Denver, CO 80202

and payment will be guaranteed by applicant or acting agent.

RECEIVED
STATE CORPORATION COMMISSION

DEC 16 1983

CONSERVATION DIVISION
Wichita, Kansas

Signed: Layle L. Robb Layle L. Robb
Applicant or Acting Agent

Date: December 14, 1983

VOYAGER



PETROLEUMS, INC.

December 14, 1983

State of Kansas
State Corporation Commission
Conservation Division
200 Colorado Derby Building
Wichita, KS 67202

Gentlemen:


Attached for you approval is Well Plugging Application Form (CP-1) requesting approval for the plug and abandonment of Voyager Petroleum, Inc.'s #34-14 McCormick well located in the SE SW Section 34, T17S, R21W, Ness County, Kansas.

The well will be plugged and abandoned in the following manner:

- 1.) Spot 20 sx sand from 4175' (PBSD) to 4025' KB (perfs at 4106'-4110' in 5½" OD, 15.5# casing). Spot 10 sx cement plug on sand from 4025' KB to 3940' KB. Spot 50 sx cement plug from 1450' KB to 1050' KB after filling casing with light mud.
- 2.) Pump 100 sx cement down 5½" OD csg and displace 5' below ground level for plug from 880' to 5'. Pump 100 sx cement down 8-5/8" OD surface casing x 5½" OD production casing annulus.
- 3.) Cut off both casing strings 5' below ground level and level location.

Voyager Petroleum, Inc. would like to commence with this work shortly after the first of the year.

Very truly yours,
VOYAGER PETROLEUMS, INC.


Layle L. Robb
Production Manager

LLR/kr

cc: Clarke Corporation
American Petrofina Company of Texas - Dallas

RECEIVED
STATE CORPORATION COMMISSION

DEC 16 1983

CONSERVATION DIVISION
Wichita, Kansas

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
200 Colorado Derby Building
202 West 1st Street
WICHITA, KANSAS 67202-1286

JOHN CARLIN
MICHAEL LENNEN
R. C. (PETE) LOUX
PHILLIP R. DICK
JUDITH MCCONNELL
BRIAN J. MOLINE

GOVERNOR
CHAIRMAN
COMMISSIONER
COMMISSIONER
EXECUTIVE SECRETARY
GENERAL COUNSEL

January 9, 1984

WELL PLUGGING NOTICE

McCormick #34-14
C SE SW
Sec. 34-17s-21W
Ness County

Voyager Petroleum Inc.
110 16th St.
Denver CO 80202

Gentlemen:

This is your notice to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This notice is void after ninety (90) days from the above date.

Yours very truly,

Carol J. Larson, Administrator

Please submit your proposal for plugging the above captioned well to

Dodge City District #1 302 West McArton Dodge City KS 67801
seven days prior to plugging the well (KAR-82-3-113)