

KANSAS CORPORATION COMMISSION RECEIVED
OIL & GAS CONSERVATION DIVISION KANSAS CORPORATION COMMISSION

Form CP-1
September 2003

This Form must be Typed
Form must be Signed
All blanks must be Filled

WELL PLUGGING APPLICATION OCT 24 2005

Please TYPE Form and File ONE Copy

CONSERVATION DIVISION
WICHITA, KS

API # 15 - 035-30198 - DD-DD (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date spud date 6-2-66

Well Operator: Gen-Dor Oil Company KCC License #: 9576 5/04

Address: 8135 281st Rd (Owner / Company Name) City: Cambridge (Operator's)

State: Kansas Zip Code: 67023 Contact Phone: (620) 467 - 2615

Lease: Mowder Well #: 4 Sec. 10 Twp. 31 S. R. 3 East West

S/2 - SW - SW - SE Spot Location / QQQQ County: Cowley

75 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

2310 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # E-12927 Other: _____

Conductor Casing Size: none Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 8 5/8 Set at: 142 feet Cemented with: 110 Sacks

Production Casing Size: 4 1/2 Set at: 3125 feet Cemented with: 100 Sacks

List (ALL) Perforations and Bridgeplug Sets: perfs are from 3064' to 3076'

Elevation: 1256 (G.L. / K.B.) T.D.: 3125' PBDT: 3081' Anhydrite Depth: Unknown (Stone Coral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): fill up bottom of well with gravel to 50 feet above the perfs
then dump bail 6 sacks of cement on top of the gravel shoot of casing and pull casing out of the well
circulat cement from depth of 300 feet (or as KCC requires) to surface

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? _____

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Ronnie Whiteman

Phone: (620) 222 - 4316 (cell #)

Address: 8135 281st Rd City / State: Cambridge, Kansas 67023

Plugging Contractor: Gen-Dor Oil Company / Company Tools KCC License #: 9576 / 99998

Address: 8135 281st Rd, Cambridge, Kansas 67023 Phone: (620) 467 - 2615

Proposed Date and Hour of Plugging (if known?): 1st week in November of 2005

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: Oct 24, 2005 Authorized Operator / Agent: Ronnie Whiteman (Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202