

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION
Please TYPE Form and File ONE Copy

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

API # 15-073-19457-0000 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date 4-27-1923

Well Operator: 3G Oil Company (Owner / Company Name) KCC License #: 31988 (Operator's)

Address: 2052 Flinthills Dr. City: Madison

State: Kansas Zip Code: 66860-8529 Contact Phone: (620) 437 - 2981

Lease: Schindler 'A' Well #: 2 Sec. 27 Twp. 23 S. R. 13 East West

SE - SE - NW Spot Location / QQQQ County: Greenwood

3334 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

2779 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well

SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: 10" Set at: 955' Cemented with: unknown Sacks

Surface Casing Size: _____ Set at: _____ Cemented with: _____ Sacks

Production Casing Size: 4 1/2" Set at: 1835' Cemented with: 100 Sacks

List (ALL) Perforations and Bridgeplug Sets: TD plug @1830' / perforated @ 1800' to 1806' & 1814' to 1818'

Elevation: _____ (G.L. / K.B.) T.D.: 1835' PBDT: 1830' Anhydrite Depth: _____ (Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): perforate 4 1/2" casing @ 720' & @ 150', put 10 sks cement on bottom pump 20 sks cement @ 720', pump 120 sks cement from 150' to G.L.

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? _____

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Virgil Johnson

Phone: (620) 437 - 7229

Address: 2052 Flinthills dr City / State: Madison, Kansas 66860-8529

Plugging Contractor: Titus Well Service (Company Name) KCC License #: 33413

Address: Box 121 Virgil, Kansas 66870 (Contractor's) Phone: (620) 678 - 3873

Proposed Date and Hour of Plugging (if known?): September 21 - 2005 8:00 am

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 9-28-05 Authorized Operator / Agent: Virgil Johnson (Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED

OCT 17 2005

KCC WICHITA

12/05

5/06

KANSAS GEOLOGICAL SOCIETY
 KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
 KANSAS GEOLOGICAL SOCIETY BUILDING
 508 EAST MURDOCK - WICHITA, KANSAS

Shindler A#2

copy

COMPANY MISSION OIL CO.

SEC. 27 T. 23 R. 13E
 LOC. C EL SE NW


FARM Shindler

NO. *X 2A*

TOTAL DEPTH 1833
 COMM. 3-29-23
 SHOT OR TREATED
 CONTRACTOR
 ISSUED

COMP. 4-27-23

COUNTY Greenwood
 KANSAS



CASING

20		10	955'
15		B $\frac{1}{4}$	1347'
12 $\frac{1}{2}$	545'	6 $\frac{5}{8}$	1609'
13		5 $\frac{3}{16}$	1775'

ELEVATION *1190 to top*

PRODUCTION 25 Bbls.

--- FIGURES INDICATE BOTTOM OF FORMATIONS

dirt	15
lime	25
slate	75
lime	85
slate	135
lime	150
slate	160
lime	170
slate	200
lime	215
slate	240
lime	250
slate	310
lime	325
slate	365
lime	375
slate	495
wtr sand	4165
slate	630
sand	640
slate	660
lime	750
slate	765
lime	795
	910
HF 215	
top red rock	949
red rock	955
shale	980
lime	1060
shale shale	1075
lime	1100
shale	1240
lime	1250
mud	1275
lime	1285
shale	1320
	1370

RECEIVED
 OCT 17 2005
 KCC WICHITA