

15-007-30141-0000

Form CP-3
Rev. 6-26-62

B

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

NOV 24 1965
11-24-65
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Amerada Petroleum Corporation

Complete Address: Box 197, Great Bend, Kansas

Lease Name Gladys Warwick Well No. # 1

Location C SW SW Sec. 4 Twp. 34 Rge. 12 (E) (W) W

County Barber Total Depth 4780'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Peel Brothers, Inc.

Address: Box 359, Hoisington, Kansas License No. _____

Operation Completed: Hour 2:00 AM Day 21st Month Nov. Year 1965

The Above well was plugged as follows:

405' of 8 5/8# surface pipe, Cemented with 300 sacks. Hole was filled
with drilling mud to 300', bridged solid with dry cement and hulls on
fluid at 300', and cemented with 25 sacks. Hole was filled with drilling
mud to 40'. 2nd cementing plug, Bridged with hulls, and cemented with 10
sacks to the base of the cellar. Rat and Mouse holes cemented with 4
sacks.

This cementing was done by Halliburton Cementing Company

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 11-29-65
INV. NO. 2263-W