

15-007-00216-0000

Form CP-3  
Rev. 6-26-62

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

SEP 30 1965  
9-30-65  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Aylward Drilling Company

Complete Address: 909 First National Bank Bldg., Wichita, Kansas

Lease Name Donovan "B" Well No. # 1

Location NE SW SW Sec. 6 Twp. 34 Rge. 12 (E) (W) W

County Barber Total Depth 4723'

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Clarke Corporation, Inc.

Address: Chapin Bldg., Medicine Lodge, Kansas License No. 583

Operation Completed: Hour 5:00 PM Day 27th Month Sept. Year 1965

The Above well was plugged as follows:

195' of 8 5/8" surface pipe, cemented with 150 sacks. 4723' of 5 1/2" long  
string, cemented with 100 sacks. Plug back to 4705'. Top perferation 4678'.  
Bottom of the hole was sanded to 4660', and cemented with 5 sacks. 1900'  
of 5 1/2" long string was recovered from the hole. Fluid in the hole was  
bailed down to 215', briège plug and rock bridge from 215' to 205', and  
cemented with 25 sacks. Hole was filled with mud to 40', bridge of rock  
from 40' to 30', and cemented with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Archie Elving  
Well Plugging Supervisor

INVOICED

DATE 9/30/65  
INV. NO. 1896-11